Add vendor CAGE 27014 for case outlines S and 2. Add case outline S. Changes to figure 4, tables I and II and group A inspection. Editorial changes throughout. Change drawing CAGE code to 67268.  B Delete Vendor CAGE 04713. Editorial changes throughout.  1990 SEP 11	
outline S. Changes to figure 4, tables I and II and group A inspection. Editorial changes throughout. Change drawing CAGE code to 67268.  B Delete Vendor CAGE 04713. Editorial changes throughout. 1990 SEP 11	W.O. 7
	14.0.2
CURRENT CAGE CODE 67268	<del>- 1 - 1 - 1 -</del>
	$\bot$
SHEET	
SHEET SHEEV SHEET	
SHEET	
SHEET	<del></del>
SHEET	PLY CENTER
SHEET	
SHEET  REV SHEET  REV STATUS OF SHEETS  SHEET  1 2 3 4 5 6 7 8 9 10 11  PREPARED BY  CHECKED BY  MILITARY  DEFENSE ELECTRONICS SUPPLICATION, OHIO 4544	14
SHEET	GH-SPEED CMOS

4 U.S. GOVERNMENT PRINTING OFFICE: 1987 — 748-129/60912

5962-E1755

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

DESC FORM 193-1 SEP 87

1. SCOPE								
1.1 Scope. This drawing describes devi	ce require	ements for class	B microcircut	its in accordance				
with 1.7.1 of MIL-STD-883, "Provisions for non-JAN devices".	the use o	of MIL-STD-883 i	onjunction	with compliant				
1.2 Part number. The complete part num	hon chall	ho as shown in	the following	ov.mnle.				
	iber Shair	De as shown in	the following	example:				
5962-86867 01		<del>R</del>	<u>)</u>	Γ-				
		1		<u> </u>				
Drawing number Device typ (1.2.1)	ē	Case outline (1.2.2)	Lead fir MIL-M-					
1.2.1 <u>Device type</u> . The device type sha	ll identif	y the circuit f	unction as fol	llows:				
Device type Generic num	ber	Ci	rcuit function	<u>1</u>				
O1 54HCT373	<b>;</b>		ee-state trans compatible in	sparent latch outs				
1.2.2 Case outlines. The case outlines shall be as designated in appendix C of MIL-M-38510, and as follows:								
Outline letter		Case outline						
R D-8 (20-1e S F-9 (20-1e 2 C-2 (20-te	ad, 1.060" ad, .540" rminal, .3	x .310" x .200" x .300" x .100" 358" x .358" x .	'), dual-in-li , flat packag .00"), square	ine package ge chip carrier package				
1.3 Absolute maximum ratings. 1/								
Supply voltage range DC input voltage DC output voltage Clamp diode current $(I_{IK}, I_{OK})$ - DC output current $(per\ pin)$ DC $V_{CC}$ or GND current $(per\ pin)$ - Storage temperature range Maximum power dissipation $(P_D)$ - Lead temperature $(soldering, 10\ sec\ Thermal\ resistance,\ junction-to-cas\ Junction\ temperature (T_J)$		-0.5 V dc to V -0.5 V dc to V ±20 mA ±35 mA ±70 mA -65°C to +150° 500 mW 2/ +300°C	(cc + 0.5 V do (cc + 0.5 V do					
1.4 Recommended operating conditions.								
Supply voltage $(V_{CC})$ Input voltage $(V_{IN})$		-55°( to +125°	5.5 V dc C					
$1/$ Unless otherwise specified, all voltag $2/$ For $T_{C}$ = +100°C to +125°C, derate line	arly at 12	erenced to groun	d.					
STANDARDIZED	SIZE <b>A</b>							
MILITARY DRAWING				5962-86867				
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LI	E <b>VEL</b> B	SHEET 2				
DECC FORM 1024		<del></del>		<del></del>				

 $\pm$  0 / S. GOVERNMENT PRINTING OF FICE, 1988  $\sim 549 \cdot 904$ 

2. APPLICABLE DOCUMENTS

2.1 Government specification, standard, and bulletin. Unless otherwise specified, the following specification, standard, and bulletin of the issue Tisted in that issue of the Department of Defense Index of Specifications and Standards specified in the solicitation, form a part of this drawing to the extent specified herein.

SPECIFICATION

MILITARY

MIL-M-38510 - Microcircuits, General Specification for.

STANDARD

MILITARY

MIL-STD-883

- Test Methods and Procedures for Microelectronics.

BULLETIN

MILITARY

MIL-BUL-103

- List of Standardized Military Drawings (SMD's).

(Lopies of the specification, standard, and bulletin required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting activity.)

- 2.2 Order of precedence. In the event of a conflict between the text of this drawing and the references cited herein, the text of this drawing shall take precedence.
  - 3. REQUIREMENTS
- $3.1\,$  Item requirements. The individual item requirements shall be in accordance with 1.2.1 of MIL-STD-883, "Provisions for the use of MIL-STD-883 in conjunction with compliant non-JAN devices" and as specified herein.
- 3.2 Design, construction, and physical dimensions. The design, construction, and physical dimensions shall be as specified in MIL-M-38510 and herein.
  - 3.2.1 <u>Terminal connections</u>. The terminal connections shall be as specified on figure 1.
  - 3.2.2 Truth table. The truth table shall be as specified on figure 2.
  - 3.2.3 Logic diagram. The logic diagram shall be as specified on figure 3.
  - 3.2.4 <u>Case outlines</u>. The case outlines shall be in accordance with 1.2.2 herein.

STANDARDIZED MILITARY DRAWING	SIZE <b>A</b>		590	62-86867	
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LEVEL	В	SHEET 3	

DESC FORM 193A SEP 87

☆ U. S. GOVERNMENT PRINTING OFFICE: 1988-549-904

TABLE I. Electrical performance characteristics. Symbol Group A Limits Unit Test Conditions  $-55^{\circ}$ C < T<sub>C</sub> < +125 $^{\circ}$ C 1/ unless otherwise specified subgroups Min I Max V<sub>CC</sub> = 4.5 V; V<sub>IN</sub> = 2.0 V or 0.8 V ٧  $|I_0| = 20 \mu A$ 1, 2, 3 4.4 High level output VOH voltage 3.7  $|I_0| = 6.0 \text{ mA}$ V<sub>CC</sub> = 4.5 V; V<sub>IN</sub> = 2.0 V or 0.8 V  $|I_0| = 20 \mu A$ 1, 2, 3 0.1 ٧ Low level output voltage VOL 0.4  $|I_0| = 6.0 \text{ mA}$  $V_{CC} = 4.5 V 2/$ ٧ 1, 2, 3 | 2.0 High level input voltage VIH 1, 2, 3 8.0 ٧ Low level input voltage  $V_{CC} = 4.5 \ V \ 2/$ VIL  $V_{CC} = GND$ ,  $T_{C} = +25$ °C, see 4.3.1c pF  $c_{\text{IN}}$ 4 10 Input capacitance  $T_C = +25^{\circ}C$ , see 4.3.1c 20 pF Output capacitance COUT  $V_{CC}$  = 5.5 V;  $V_{IN}$  =  $V_{CC}$  or GND  $I_{OUT}$  = 0.0 A  $\mu \, A$ 1, 2, 3 160 Quiescent current ICC 1, 2, 3 ±1.0 μА  $V_{CC} = 5.5 \text{ V}$ ;  $V_{IN} = V_{CC} \text{ or GND}$ Input leakage current IIN Functional tests See 4.3.1d 7, 8  $\begin{array}{l} v_{CC} = 5.5 \text{ V} \\ v_{IN} = 2.0 \text{ V or } 0.8 \text{ V,} \\ v_{O} = v_{CC} \text{ or GND} \\ \end{array}$ Three-state output  $I_{0Z}$ 1, 2, 3 ±10 μΑ current Any 1 input: VIN = 2.4 V or 0.5 V Other inputs: 1, 2, 3 Additional quiescent VI CC 3.0 mΑ supply current V<sub>IN</sub> = V<sub>CC</sub> or GND I<sub>OUT</sub> = 0.0 A V<sub>CC</sub> = 5.5 V See footnotes at end of table. **STANDARDIZED** SIZE Α 5962-86867 **MILITARY DRAWING DEFENSE ELECTRONICS SUPPLY CENTER REVISION LEVEL** SHEET DAYTON, OHIO 45444 4

DESC FORM 193A SEP 87

± U.S. GOVERNMENT PRINTING OFFICE: 1988 -549-904

		trical performance characteristics -		<del>,</del>		
Test Symbo		Conditions	Group A		mits	! ! Unit
		-55°C < T <sub>C</sub> < +125°C 1/ unless otherwise specified	subgroups	Min	Max	<u> </u>
Propagation delay,	t <sub>PHL1</sub> ,	Vcc = 5.0 V,	9 1	1	1 35	ns
D to Q	t <sub>PLH1</sub>	CL = 50 pF,   See figure 4	10, 11	1	53	ns
Propagation delay,	tpLZ,		9		35	ns
output disable time, OUTPUT ENABLE to Q			10, 11	<u> </u>	53	ns
Propagation delay,	t <sub>PZL</sub> ,		9	!	35	ns
output enable time, OUTPUT ENABLE to Q	t <sub>PZH</sub>	1	10, 11	<u> </u>	53	l ns
Propagation delay,	t <sub>PHL2</sub> ,	ļ	9	·	1 35	l ns
LATCH ENABLE to Q	t <sub>PLH2</sub>	1	10, 11		53	ns
Transition time 3/	t <sub>TLH</sub> ,		9	_ <del></del>	1 12	l ns
	t <sub>THL</sub>	1	10, 11		18	ns

- For a power supply of 5 V ±10 percent, the worst case output voltages (V $_{OH}$  and V $_{OL}$ ) occur for HCT at 4.5 V. Thus, the 4.5 V values should be used when designing with this supply. Worst cases V $_{IH}$  and V $_{IL}$  occur at V $_{CC}$  = 5.5 V and 4.5 V respectively. V $_{IH}$  and V $_{IL}$  are not required and shall be applied as forcing functions for V $_{OH}$  or V $_{OL}$  tests. Transition time (t $_{TLH}$ , t $_{THL}$ ), if not tested, shall be guaranteed to the specified limits.
- 3.3 Electrical performance characteristics. Unless otherwise specified herein, the electrical performance characteristics are as specified in table I and apply over the full case operating temperature range.
- 3.4 Electrical test requirements. The electrical test requirements shall be the subgroups specified in table II. The electrical tests for each subgroup are described in table I.
- 3.5 Marking. Marking shall be in accordance with MIL-STD-883 (see 3.1 herein). The part shall be marked with the part number listed in 1.2 herein. In addition, the manufacturer's part number may also be marked as listed in MIL-BUL-103 (see 6.6 herein).
- 3.6 Lertificate of compliance. A certificate of compliance shall be required from a manufacturer in order to be listed as an approved source of supply in MIL-BUL-103 (see 6.6 herein). The certificate of compliance submitted to DESC-ECC prior to listing as an approved source of supply shall affirm that the manufacturer's product meets the requirements of MIL-STD-883 (see 3.1 herein) and the requirements herein.
- 3.7 Certificate of conformance. A certificate of conformance as required in MIL-STD-883 (see 3.1 herein) shall be provided with each lot of microcircuits delivered to this drawing.

STANDARDIZED MILITARY DRAWING	SIZE A		5:	962-86867	
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LEVEL		SHEET 5	

17 U. S. GOVERNMENT PRINTING OFFICE: 1988--549-904

Device type	01		
Case outlines	R, S, and 2		
Terminal number	Terminal symbol		
1	OUTPUT ENABLE		
2	QO		
3	DO		
4	D1		
5	Q1		
6	Q2		
7	D2		
8	D3		
9	Q3		
10	GND		
11	LATCH ENABLE		
12	Q4		
13	D4		
14	D5		
15	Q5		
16	Q6		
17	D6		
18	D7		
19	Q7		
20	VCC		

FIGURE 1. Terminal connections.

STANDARDIZED
MILITARY DRAWING
DEFENSE ELECTRONICS SUPPLY CENTER
DAYTON, OHIO 45444

SIZE
A
5962-86867

REVISION LEVEL
B
6

DESC FORM 193A SEP 87


2 U. S. GOVERNMENT PRINTING OFFICE: 1988---549 904

OUTPUT ENABLE	LATCH ENABLE	Data	Output
L L L	H H L X	H L X	H L Qo Z

 $\begin{array}{ll} \text{H = High level, L = Low level} \\ \text{Q}_0 = \text{Level of output before steady-state input} \\ & \text{conditions were established} \end{array}$ 


Z = High impedance

FIGURE 2. Truth table.



DESC FORM 193A SEE 87

⊕ U. S. GOVERNMENT PRINTING OFFICE 1989 749-033



 $\delta(U,S)$  GOVERNMENT PRINCIPLE OFFICE THEY. WE GOT

- 3.8 Notification of change. Notification of change to DESC-ECC shall be required in accordance with MIL-STD-883 (see 3.1 herein).
- 3.9 <u>Verification and review.</u> DESC, DESC's agent, and the acquiring activity retain the option to review the manufacturer's facility and applicable required documentation. Offshore documentation shall be made available onshore at the option of the reviewer.
  - 4. QUALITY ASSURANCE PROVISIONS
- 4.1 Sampling and inspection. Sampling and inspection procedures shall be in accordance with section 4 of MIL-M-38510 to the extent specified in MIL-STD-883 (see 3.1 herein).
- 4.2 Screening. Screening shall be in accordance with method 5004 of MIL-STD-883, and shall be conducted on all devices prior to quality conformance inspection. The following additional criteria shall apply:
  - a. Burn-in test, method 1015 of MIL-STD-883.
    - (1) Test condition A, B, C, or D using the circuit submitted with the certificate of compliance (see 3.6 herein).
    - (2)  $T_A = +125$ °C, minimum.
  - b. Interim and final electrical test parameters shall be as specified in table II herein, except interim electrical parameter tests prior to burn-in are optional at the discretion of the manufacturer.

TABLE II. Electrical test requirements.

     MIL-STD-883 test requirements 	Subgroups   (per method   5005, table I)
Interim electrical parameters (method 5004)	
Final electrical test parameters (method 5004)	1*, 2, 3, 7, 8, 9
Group A test requirements (method 5005)	1, 2, 3, 4, 7,     8, 9, 10**, 11**
Groups C and D end-point electrical parameters (method 5005)	1, 2, 3

- \* PDA applies to subgroup 1.
- \*\* Subgroups 10 and 11, if not tested, shall be guaranteed to the specified limits in table I.

4.3 Quality conformance inspection. Quality conformance inspection shall be in accordance with method 5005 of MIL-SID-883 including groups A, B, C, and D inspections. The following additional criteria shall apply.

STANDARDIZED MILITARY DRAWING	Size <b>A</b>		590	62-86867	
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LEVEL	В	SHEET 9	

DESC FORM 193A SEP 87

± U. S. GOVERNMENT PRINTING OFFICE, 1988--549-904

- 4.3.1 Group A inspection.
  - a. Tests shall be as specified in table II herein.
  - b. Subgroups 5 and 6 in table I, method 5005 of MIL-STD-883 shall be omitted.
  - c. Subgroup 4 (CIN and COUT measurements) shall be measured only for the initial test and after process or design changes which may affect capacitance. Capacitance shall be measured between the designated terminal and GND at a frequency of 1 MHz. Test all applicable pins on five devices with zero failures.
  - d. Subgroups 7 and 8 tests shall verify the truth table as specified on figure 2.
- 4.3.2 Groups C and D inspections.
  - a. End-point electrical parameters shall be as specified in table II herein.
  - b. Steady-state life test conditions, method 1005 of MIL-STD-883.
    - Test condition A, B, C, or D using the circuit submitted with the certificate of compliance (see 3.6 herein).
    - (2)  $T_A = +125$ °C, minimum.
    - (3) Test duration: 1,000 hours, except as permitted by method 1005 of MIL-STD-883.
- 5. PACKAGING
- 5.1 Packaging requirements. The requirements for packaging shall be in accordance with MIL-M-38510.
  - 6. NOTES
- 6.1 Intended use. Microcircuits conforming to this drawing are intended for use when military specifications do not exist and qualified military devices that will perform the required function are not available for OEM application. When a military specification exists and the product covered by this drawing has been qualified for listing on QPL-38510, the device specified herein will be inactivated and will not be used for new design. The QPL-38510 product shall be the preferred item for all applications.
- 6.2 Replaceability. Microcircuits covered by this drawing will replace the same generic device covered by a contractor-prepared specification or drawing.
- 6.3 Configuration control of SMD's. All proposed changes to existing SMD's will be coordinated with the users of record for the individual documents. This coordination will be accomplished in accordance with MIL-STD-481 using DD Form 1693, Engineering Change Proposal (Short Form).
- 6.4 Record of users. Military and industrial users shall inform Defense Electronics Supply Center when a system application requires configuration control and the applicable SMD. DESC will maintain a record of users and this list will be used for coordination and distribution of changes to the drawings. Users of drawings covering microelectronics devices (FSC 5962) should contact DESC-ECS, telephone (513) 296-6022.
- 6.5 Comments. Comments on this drawing should be directed to DESC-ECS, Dayton, Ohio 45444, or telephone (513) 296-5375.

STANDARDIZED MILITARY DRAWING	SIZE A		59	62-86867
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LEVE	L B	SHEET 10

b.6 Approved sources of supply. Approved sources of supply are listed in MIL-BUL-103. Additional sources will be added to MIL-BUL-103 as they become available. The vendors listed in MIL-BUL-103 have agreed to this drawing and a certificate of compliance (see 3.6 herein) has been submitted to and accepted by DESC-ECS. The approved sources listed below are for information purposes only and are current only to the date of the last action of this document.

Military drawing part number	Vendor   CAGE   number	Vendor   similar part   number <u>1</u> /
5962-8686701RX	01295 34371 27014	SNJ54HCT373J   CD54HCT373F/3A   MM54HCT373J/883
5962 -8686701 SX	27014	   MM54HCT373W/883
5962-86867012X	01295	SNJ54HCT373FK   MM54HCT373E/883

1/ Caution. Do not use this number for item acquisition. Items acquired to this number may not satisfy the performance requirements

Vendor CAGE Vendor name and address number Texas Instruments, Incorporated 13500 North Central Expressway 01295 P.O. Box 655303 Dallas TX 75265 Point of contact: I-20 at FM 1788 Midland, TX 79711-0448 27014 National Semiconductor 2900 Semiconductor Drive P.O. Box 58090 Santa Clara, CA 95052-8090 Point of contact: 333 Western Avenue South Portland, ME 04106 34371 Harris Semiconductor P.O. Box 883 Melbourne, FL 32901

STANDARDIZED
MILITARY DRAWING
DEFENSE ELECTRONICS SUPPLY CENTER
DAYTON, OHIO 45444

DESC FORM 193A SEP 87

☆ U. S. GOVERNMENT PRINTING OFFICE. 1988 -549-904